

ELECTRICAL WORKS						
Sr NO	SERVICE CODES	DESCRIPTION	Long Description	WBS	UOM	RATES
1	ELE-R&M-001	SUP&LAY XLPE/AYFY 1.1KV CBL 4CX16MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , inner extruded PVC sheath , 3.5/4 CORE, ARMOURED, stranded ALUMINIUM conductor cables of 1.1KV 'class cables per IS 7098 Part -1	ELECTRICAL	Mtrs	258.00
2	ELE-R&M-002	PWR CKT LAY 2X2.5+1X1.5MM2,25 DIA,PVC CD	2 x 2.5 + 1 x 1.5 sqmm	ELECTRICAL	Mtrs	180.00
3	ELE-R&M-003	PWR CKT LAY 2X4.0+1X2.5MM2 CU WIRE	2 x 4.0 + 1 x 2.5 sqmm	ELECTRICAL	Mtrs	250.00
4	ELE-R&M-004	S&I OF APRV RUBBER MAT F/1.1KV	Supply installation of Rubber mat suitable for operatngvoltage up to 1.1 KV	ELECTRICAL	Nos	1,825.00
5	ELE-R&M-005	S&I OF TPN 100 A MCCB 25KA	Supply, installation, testing & commissioning of TPN, 415V, 25KA MCCB . 100 A MCCB, TPN, 25KA	ELECTRICAL	Nos	7,000.00
6	ELE-R&M-006	SUP&INST OF TPN 125 A MCCB 25KA	Supply & Installation of TPN, manual MCCB, 25 KA 125 A MCCB,TPN,25KA	ELECTRICAL	Nos	9,000.00
9	ELE-R&M-009	SUP&LAY CBL 1.1KV ARM XLPE AL 4CX10MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , inner extruded PVC sheath , 3.5/4 CORE, ARMOURED, stranded ALUMINIUM conductor cables of 1.1KV 'class cables	ELECTRICAL	Mtrs	223.00
10	ELE-R&M-010	SUP&LAY CBL 1.1KV ARM XLPE AL 3.5CX25MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , inner extruded PVC sheath , 3.5/4 CORE, ARMOURED, stranded ALUMINIUM conductor cables of 1.1KV 'class cables	ELECTRICAL	Mtrs	311.00
11	ELE-R&M-011	SUP&LAY CBL 1.1KV ARM XLPE AL 3.5CX35MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , inner extruded PVC sheath ,3.5/4 CORE ARMOURED stranded ALUMINIUM conductor cables of 1.1KV 'class cables. 3.5C X 35 sq.mm AL	ELECTRICAL	Mtrs	383.00
12	ELE-R&M-012	SUP&LAY CBL 1.1KV ARM XLPE AL 3.5CX50MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , inner extruded PVC sheath , 3.5/4 CORE, ARMOURED, stranded ALUMINIUM conductor cables of 1.1KV 'class cables. Size : 3.5C X 50 sq.mm AL	ELECTRICAL	Mtrs	457.00
13	ELE-R&M-013	SUP&LAY CBL 1.1KV UA XLPE CU 4CX6MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , inner extruded PVC sheath ,UNARMOURED, stranded COPPER conductor cables of 1.1KV 'class cables	ELECTRICAL	Mtrs	510.00
14	ELE-R&M-014	SUP&LAY CBL 1.1KV UA XLPE CU 3CX2.5MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , inner extruded PVC sheath ,UNARMOURED, stranded COPPER conductor cables of 1.1KV 'class cables	ELECTRICAL	Mtrs	208.50
15	ELE-R&M-015	SUP&LAY CBL 1.1KV UA XLPE CU 1CX25MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , inner extruded PVC sheath ,UNARMOURED, stranded COPPER conductor cables of 1.1KV 'class cables Size: 1cx25 mm2	ELECTRICAL	Mtrs	375.00
16	ELE-R&M-016	SUP&LAY CBL 1.1KV UA XLPE CU 1CX16MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , inner extruded PVC sheath ,UNARMOURED, stranded COPPER conductor cables of 1.1KV 'class cables	ELECTRICAL	Mtrs	286.00
17	ELE-R&M-017	SUP&LAY CBL 1.1KV UA XLPE CU 1CX10MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , inner extruded PVC sheath ,UNARMOURED, stranded COPPER conductor cables of 1.1KV 'class cables Size: CU 1Cx10 mm2	ELECTRICAL	Mtrs	178.00
18	ELE-R&M-018	SUP&LAY CBL 1.1KV ARM XLPE CU 4CX6MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , inner extruded PVC sheath ,ARMOURED, stranded COPPER conductor cables of 1.1KV 'class cables	ELECTRICAL	Mtrs	528.50
19	ELE-R&M-019	SUP&LAY CBL 1.1KV ARM XLPE CU 4CX4MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , inner extruded PVC sheath ,ARMOURED, stranded COPPER conductor cables of 1.1KV 'class cables	ELECTRICAL	Mtrs	399.00
20	ELE-R&M-020	SUP&LAY CBL 1.1KV ARM XLPE CU 4CX2.5MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , inner extruded PVC sheath ,ARMOURED, stranded COPPER conductor cables of 1.1KV 'class cables	ELECTRICAL	Mtrs	278.50

ELECTRICAL WORKS						
Sr NO	SERVICE CODES	DESCRIPTION	Long Description	WBS	UOM	RATES
21	ELE-R&M-021	SUP&LAY CBL 1.1KV ARM XLPE CU 3CX4MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , inner extruded PVC sheath ,ARMOURED, stranded COPPER conductor cables of 1.1KV 'class cables	ELECTRICAL	Mtrs	358.00
22	ELE-R&M-022	SUP&LAY CBL 1.1KV ARM XLPE CU 3CX2.5MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , inner extruded PVC sheath Supply and Laying of XLPE insulated FR PVC outer sheathed , inner extruded PVC sheath ,ARMOURED, stranded COPPER conductor cables of 1.1KV 'class cables	ELECTRICAL	Mtrs	271.00
23	ELE-R&M-023	SUP&FIX SHK TRTMNT CHRT&DANGER BOARD	supply and fixing in position approved shock treatment chart written in English, Hindi and in local Language	ELECTRICAL	Nos	492.00
24	ELE-R&M-024	SUP OF APR HAND GLOVES F/OP V 1.1KV	Supply & Installation of Rubber Hand Gloves, CPRI tested conforming to standards like IS 4770 for different operating voltage ratings as below. Hand Gloves suitable for operating voltage upto 1.1 KV	ELECTRICAL	Nos	500.00
25	ELE-R&M-025	SUP&FIX OF FIRST AID BOX	Supply and installtion of First Aid Box	ELECTRICAL	Nos	600.00
26	ELE-R&M-026	SUP& INST 63A DP MCB IN DB	Supply, installation, testing and commissioning of 63A DP MCB	ELECTRICAL	Nos	1,538.00
27	ELE-R&M-027	SUP&INST OF25MM MS CONDUIT B CLASS W/ACC	Supplying and installation of 25 mm Dia, Class B Black enamelled Rigid MS conduit	ELECTRICAL	Mtrs	140.00
28	ELE-R&M-028	SITC IP42 4 WAY VTPNDB W/125A MCCB INCOM	Supply, Installation , testing & Commissioning of various Distribution Boards (DB) - Make - Legrand 4 WAY VTPN DB	ELECTRICAL	Nos	11,566.00
29	ELE-R&M-029	SITC APRV 6A,SP,230V,10KA,C TYPE MCB	Supply, Installation , testing & Commissioning of 6A,SP,230V,10KA,C TYPE MCB (MINIATURE CIRCUIT BREAKER)	ELECTRICAL	Nos	286.00
30	ELE-R&M-030	SITC 12 WAY SPN DB	Supply, Installation , testing & Commissioning of various Distribution Boards (DB) - wall mounted Make - Legrand 12 WAY SPN DB	ELECTRICAL	Nos	3,372.00
31	ELE-R&M-031	SITC 16 WAY SPN DB	Supply, Installation , testing & Commissioning of various Distribution Boards (DB) - . Make - Legrand 16 WAY SPN DB	ELECTRICAL	Nos	3,850.00
32	ELE-R&M-032	SITC APRV WM 8 WAY TPN DB,7SEG PH SEG	Supply, Installation , testing & Commissioning of various Distribution Boards (DB) - Make - Legrand 8 WAY TPN DB,	ELECTRICAL	Nos	10,831.00
33	ELE-R&M-033	SITC APRV WM 12 WAY TPN DB,7SEG PH SEG	Supply, Installation , testing & Commissioning of various Distribution Boards (DB) - Make - Legrand 12 WAY TPN DB	ELECTRICAL	Nos	12,241.00
34	ELE-R&M-034	SITC IP42 8WAY VTPN DB W/125A MCCB INCOM	Supply, Installation , testing & Commissioning of various Distribution Boards (DB) - Make - Legrand 8 WAY VTPN DB	ELECTRICAL	Nos	11,507.00
35	ELE-R&M-035	SITC APRV 10A,SP,230V,10KA,C TYPE MCB	Supply, Installation , testing & Commissioning of 10A,SP,230V,10KA,C TYPE MCB (MINIATURE CIRCUIT BREAKER)	ELECTRICAL	Nos	286.00
36	ELE-R&M-036	SITC APRV 16A,SP,230V,10KA,C TYPE MCB	Supply, Installation , testing & Commissioning of 16A,SP,230V,10KA,C TYPE MCB (MINIATURE CIRCUIT BREAKER)	ELECTRICAL	Nos	301.00
37	ELE-R&M-037	SITC APRV 25A,SP,230V,10KA,C TYPE MCB	Supply, Installation , testing & Commissioning of 25A,SP,230V,10KA,C TYPE MCB (MINIATURE CIRCUIT BREAKER)	ELECTRICAL	Nos	301.00
38	ELE-R&M-038	SITC APRV 32A,SP,230V,10KA,C TYPE MCB	Supply, Installation , testing & Commissioning of 32A,SP,230V,10KA,C TYPE MCB (MINIATURE CIRCUIT BREAKER)	ELECTRICAL	Nos	322.00
39	ELE-R&M-039	SITC APRV 25A,DP,230V,10KA,C TYPE MCB	Supply, Installation , testing & Commissioning of 25A,DP,230V,10KA,C TYPE MCB (MINIATURE CIRCUIT BREAKER)	ELECTRICAL	Nos	756.00
40	ELE-R&M-040	SITC APRV 32A,DP,230V,10KA,C TYPE MCB	Supply, Installation , testing & Commissioning of 32A,DP,230V,10KA,C TYPE MCB (MINIATURE CIRCUIT BREAKER)	ELECTRICAL	Nos	780.00
41	ELE-R&M-041	SITC APRV 40A,DP,230V,10KA,C TYPE MCB	Supply, Installation , testing & Commissioning of 40A,DP,230V,10KA,C TYPE MCB (MINIATURE CIRCUIT BREAKER)	ELECTRICAL	Nos	1,168.00
42	ELE-R&M-042	SITC APRV 63A,DP,230V,10KA,C TYPE MCB	Supply, Installation , testing & Commissioning of 63A,DP,230V,10KA,C TYPE MCB(MINIATURE CIRCUIT BREAKER)	ELECTRICAL	Nos	1,196.00
43	ELE-R&M-043	SITC APRV 16A,TP,415V,10KA,C TYPE MCB	Supply, Installation , testing & Commissioning of 16A,TP,415V,10KA,C TYPE MCB(MINIATURE CIRCUIT BREAKER)	ELECTRICAL	Nos	1,163.00

ELECTRICAL WORKS						
Sr NO	SERVICE CODES	DESCRIPTION	Long Description	WBS	UOM	RATES
44	ELE-R&M-044	SITC APRV 32A,TP,415V,10KA,C TYPE MCB	Supply, Installation , testing & Commissioning of 32A,TP,415V,10KA,C TYPE MCB(MINIATURE CIRCUIT BREAKER)	ELECTRICAL	Nos	1,216.00
45	ELE-R&M-045	SITC APRV 40A,TP,415V,10KA,C TYPE MCB	Supply, Installation , testing & Commissioning of 40A,TP,415V,10KA,C TYPE MCB(MINIATURE CIRCUIT BREAKER)	ELECTRICAL	Nos	1,790.00
46	ELE-R&M-046	SITC APRV 63A,TP,415V,10KA,C TYPE MCB	Supply, Installation , testing & Commissioning of 63A,TP,415V,10KA,C TYPE MCB(MINIATURE CIRCUIT BREAKER)	ELECTRICAL	Nos	1,790.00
47	ELE-R&M-047	SITC APRV 40A,TPN,415V,10KA,C TYPE MCB	Supply, Installation , testing & Commissioning of 40A,TPN,415V,10KA,C TYPE MCB(MINIATURE CIRCUIT BREAKER)	ELECTRICAL	Nos	2,016.00
48	ELE-R&M-048	SITC APRV 63A,TPN,415V,10KA,C TYPE MCB	Supply, Installation , testing & Commissioning of 63A,TPN,415V,10KA,C TYPE MCB(MINIATURE CIRCUIT BREAKER)	ELECTRICAL	Nos	2,058.00
49	ELE-R&M-049	SITC APRV 16A,FP,415V,10KA,C TYPE MCB	Supply, Installation , testing & Commissioning of 16A,FP,415V,10KA,C TYPE MCB(MINIATURE CIRCUIT BREAKER)	ELECTRICAL	Nos	1,398.00
50	ELE-R&M-050	SITC APRV 40A,FP,415V,10KA,C TYPE MCB	Supply, Installation , testing & Commissioning of 40A,FP,415V,10KA,C TYPE MCB(MINIATURE CIRCUIT BREAKER)	ELECTRICAL	Nos	2,054.00
51	ELE-R&M-051	SITC 6A 3PIN SWITCH&SOCKE W/MB FLS MOUNT	Supply, installation, testing and commissioning of 6A, 3 pin switch and socket on modular board	ELECTRICAL	Nos	569.00
52	ELE-R&M-052	SITC 6/16A 5PIN SWIT&SOCK W/MB FLS MOUNT	Supply, installation, testing and commissioning of 6/16A, 5 pin switch & socket on modular board	ELECTRICAL	Nos	707.00
53	ELE-R&M-053	SUP&LAY CBL 1.1KV ARM XLPE CU 3CX6MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , inner extruded PVC sheath ,ARMOURED, stranded COPPER conductor cables of 1.1KV 'class cables	ELECTRICAL	Mtrs	343.50
54	ELE-R&M-054	SUP&LAY CBL 1.1KV AL ARM XLPE 3CX10MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , inner extruded PVC sheath , 3CORE, ARMOURED, stranded ALUMINIUM conductor cables of 1.1KV 'class cables 3C X 10 sq.mm AL	ELECTRICAL	Mtrs	244.00
55	ELE-R&M-055	SITC 8 WAY SPN DB	Supply, Installation , testing & Commissioning of various Distribution Boards (DB) - Make - Legrand 8 WAY SPN DB	ELECTRICAL	Nos	2,828.00
56	ELE-R&M-056	SITC 25A,DP230V10KA30MA,RCCBWO O/L+S/CPR	Supply, Installation , testing & Commissioning of 25A, DP, 230V, 10KA, 30mA, RESIDUAL CURRENT CIRCUIT BREAKER WITHOUT O/L + S/C PROTECTION	ELECTRICAL	Nos	2,035.00
57	ELE-R&M-057	S&I APR SPIKEGUARD W/6NOS 3PIN SKT W/1SW	Supply and installation of Spike Guard with six (6) nos universal type 3 pin socket outlets with one control switch, inbuilt Fuse and indicator and a chord with a 3 pin 16 A plug top suitable to fit into a 5 pin 6/16 A socket outlet	ELECTRICAL	Nos	1,850.00
58	ELE-R&M-058	SITC OF 4 POLE METAL ENCLOSURE	Supply, installation, testing & commissioning of 4 pole CRCA sheet metal enclosure Make - Legrand/Havels/Siemens/Schneider.	ELECTRICAL	Nos	842.00
59	ELE-R&M-059	SITC OF SQ. DOWNLIGHTER,20W	SUPPLY INSTALLATION TESTING AND COMMISSIONING of 20Watt LED Square Down lighter	ELECTRICAL	Nos	1,140.00
60	ELE-R&M-060	SITC APRV 25A,TPN,415V,10KA,C TYPE MCB	Supply, Installation , testing & Commissioning of 25A,TPN,415V,10KA,C TYPE MCB(MINIATURE CIRCUIT BREAKER)	ELECTRICAL	Nos	1,560.00
61	ELE-R&M-061	SUP&LAY CBL 1.1KV ARM XLPE AL 3CX16MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , inner extruded PVC sheath , 3CORE, ARMOURED, stranded ALUMINIUM conductor cables of 1.1KV '	ELECTRICAL	Mtrs	256.00
62	ELE-R&M-062	SUP&LAY CBL 1.1KV UA XLPE CU 4CX10MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , inner extruded PVC sheath , UNARMOURED, stranded COPPER conductor cables of 1.1KV 'class cables	ELECTRICAL	Mtrs	714.00
63	ELE-R&M-063	SUP&LAY CBL 1.1KV PVC CU 3CX6MM2	Supply and Laying of 1.1 KV Grade PVC insulated FLEXIBLE cable with copper conductor 3C x 6 sq mm Cu	ELECTRICAL	Mtrs	298.50
64	ELE-R&M-064	SUP&LAY CBL 1.1KV UA XLPE CU 3CX4MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , inner extruded PVC sheath , UNARMOURED, stranded COPPER conductor cables of 1.1KV 'class cables	ELECTRICAL	Mtrs	259.00

ELECTRICAL WORKS						
Sr NO	SERVICE CODES	DESCRIPTION	Long Description	WBS	UOM	RATES
65	ELE-R&M-065	SUP,INST&TST OF CT/PT OPRTD ENERGY METER	Supply & installation of Energymeter with CT/PT in MS enclosure	ELECTRICAL	Nos	13,619.00
66	ELE-R&M-066	SITC APRV 25A,TP,415V,10KA,C TYPE MCB	Supply, Installation , testing & Commissioning of 25A,TP,415V,10KA,C TYPE MCB(MINIATURE CIRCUIT BREAKER)	ELECTRICAL	Nos	1,216.00
67	ELE-R&M-067	SITC PLG&SOKT DB W/25A FP MCB IN ENCL&AC	Supply, installation, testing and commissioning of 25 A FP MCB in metal enclosure	ELECTRICAL	Nos	2,246.00
68	ELE-R&M-068	SUP&INST OF TPN 200A MCCB 25KA	Supply & Installation of TPN, manual MCCB, 200 A MCCB,TPN,25KA	ELECTRICAL	Nos	12,609.00
69	ELE-R&M-069	SUP&LAY CTR CBL 1.1KV UA CU 2CX1.5MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , inner extruded PVC sheath , UNARMoured, stranded COPPER conductor cables of 1.1KV 'class cables	ELECTRICAL	Mtrs	132.00
70	ELE-R&M-070	SITC OF CALL BELL WITH PUSH SWITCH	Supply, installation, testing & commissioning of single /multi tone call bell with bell push switch. Material Make # Anchor/Legrand/Havel/ Vaishnavi /L&T/Schneider/Siemens etc.	ELECTRICAL	Nos	738.00
71	ELE-R&M-071	SUP&LAY CBL 1.1KV ARM XLPE AL 3CX25MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , inner extruded PVC sheath , 3CORE, ARMoured, stranded ALUMINIUM conductor cables of 1.1KV 'class cables	ELECTRICAL	Mtrs	316.00
72	ELE-R&M-072	SITC PLUG & SOKET DB 63 A FP RCBO W/ENCL	Supply, installation, testing and commissioning of Plug and socket DBs 63 A FP RCBO in metal enclosure	ELECTRICAL	Nos	4,575.00
73	ELE-R&M-073	SITC PLUG & SOKET DB 16 A DP RCBO W/ENCL	Supply, installation, testing and commissioning of Plug and socket DBs 63 A FP RCBO in metal enclosure	ELECTRICAL	Nos	3,055.00
74	ELE-R&M-074	SUP&INST OF TPN 160 A MCCB 25KA	Supply, installation, testing & commissioning of TPN, 415V, 25KA MCCB . 160 A MCCB, TPN, 25KA	ELECTRICAL	Nos	11,667.00
75	ELE-R&M-075	SUPPLY&INSTALLATION OF 15A PLUG TOP	Supply and Installation of 15 amps.	ELECTRICAL	Nos	166.00
76	ELE-R&M-076	SITC OF 2FTX2FT 40 W LED REC LUM INARE	Supply, Installation, testing & Commissioning of 36-40W LED, 2Ft X 2Ft Make #Hybec/Light book/PMEA/Bajaj/Asian Retail/Wipro/Argo,Phillips/Halonix	ELECTRICAL	Nos	2,950.00
77	ELE-R&M-077	SITC OF 20 W / 22 W LED, CIR REC ,5700K	Supply, Installation, testing & Commissioning of 20 W / 22 W LED, Circular Recessed mounted luminaire Make #Hybec/Light book/PMEA/Bajaj/Asian Retail/Wipro/Argo,Phillips/Halonix	ELECTRICAL	Nos	1,425.00
78	ELE-R&M-078	S&L APRV PVC FLEXIBL CBL1.1KV CU 4CX4MM2	Supply and Laying of 1.1 KV Grade PVC insulated FLEXIBLE cable with copper conductor as per IS - 694. 4C x 4 sq mm Cu	ELECTRICAL	Mtrs	315.00
79	ELE-R&M-079	S&L APRV PVC FLEXIBL CBL1.1KV CU 4CX6MM2	Supply and Laying of 1.1 KV Grade PVC insulated FLEXIBLE cable with copper conductor as per IS - 694. 4C x 6 sq mm Cu	ELECTRICAL	Mtrs	392.00
80	ELE-R&M-080	SITC 32A TP PLG&SCKT W/32A DP MCB	Supply, installation, testing and commissioning of Plug and socket 32 A, 3 pin socket outlet with 32 A DP MCB in metal enclosure	ELECTRICAL	Nos	2,790.00
81	ELE-R&M-081	S&L APRV PVC FLEXIBL CBL1.1KV CU3CX10MM2	Supply and Laying of 1.1 KV Grade PVC insulated , ZERO SMOKE HALOGEN FREE FLEXIBLE cable with copper conductor 3C x 10 sq. mm Cu	ELECTRICAL	Mtrs	627.00
82	ELE-R&M-082	S&L APRV PVC FLEXIBL CBL1.1KV CU3CX16MM2	Supply and Laying of 1.1 KV Grade PVC insulated FLEXIBLE ZERO SMOKE HALOGEN FREE cable with copper conductor 3C x 16 sq. mm Cu	ELECTRICAL	Mtrs	958.00
83	ELE-R&M-083	SF CIR BR MCB DP 16A 230V 10KA C TYPE	Supply and fixing of CIR BR MCB DP 16A 230V 10KA C TYPE	ELECTRICAL	Nos	760.00
84	ELE-R&M-084	SITC 20 WAY SPN DB	Supply, Installation, testing & Commissioning of various Distribution Boards (DB) 20WAY SPN DB	ELECTRICAL	Nos	4,888.00

ELECTRICAL WORKS						
Sr NO	SERVICE CODES	DESCRIPTION	Long Description	WBS	UOM	RATES
85	ELE-R&M-085	SUP&LAY CBL 1.1KV ARM XLPE AL 4CX25MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , innerextruded PVC sheath , armoured, stranded Al conductor cables of 1.1KV 'class cables per IS	ELECTRICAL	Mtrs	382.00
86	ELE-R&M-086	S&L XLPE/INS FR PVC SH 1.1KV CBL4CX50MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , innerextruded PVC sheath , AL types of conductor cables of 1.1KV 'classcables4C X 50 sq.mm AL	ELECTRICAL	Mtrs	695.50
87	ELE-R&M-087	SUP&LAY CBL 1.1KV ARM XLPE AL 4CX35MM2	4 core 35 sqmm Al Cable	ELECTRICAL	Mtrs	554.00
88	ELE-R&M-088	SUP&LAY CBL 1.1KV UA XLPE CU 1CX6MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , innerextruded PVC sheath ,UNARMOURED, stranded COPPER conductor cables of 1.1KV 'class cables	ELECTRICAL	Mtrs	146.00
89	ELE-R&M-089	SUP&FIX OF FIRE EXTINGUISHER 4.5KG	Supply and fixing in position DCP fire extinguisher 4.5 kg	ELECTRICAL	Nos	2,463.00
90	ELE-R&M-090	SITC PLG&SOKT DB W/63A FP MCB IN ENCL&AC	Supply, installation, testing and commissioning of 63 A FP MCB in metal enclosure	ELECTRICAL	Nos	3,067.00
91	ELE-R&M-091	SITC PLUG&SOCK DB W/40A 4P MCB &MET ENCL	POWER RECEPTACLESupply, installation, testing and commissioning of 40A 4P MCB in metal enclosure - weather proof	ELECTRICAL	Nos	2,972.00
92	ELE-R&M-092	SITC RCBO, 25A,DP, 230V,10KA 30MA,	Supply, Installation , testing <(>&<)> Commissioning DB's.25A, DP, 230V, 10KA, 30mA, RCBO	ELECTRICAL	Nos	2,427.00
93	ELE-R&M-093	SITC PLG&SOKT DB W/32A FP MCB IN ENCL&AC	Supply, installation, testing and commissioning of 32 A FP MCB in metal enclosure	ELECTRICAL	Nos	1,993.00
94	ELE-R&M-094	SITC PLUG&SOCK DB W/3X5ASOCK&1X16A SWITC	Supply, installation, testing and commissioning of Supply <(>&<)> installation of 3 NOS. 5A SOCKET CONTROL BY 1NO. 16 AMPSWITCH	ELECTRICAL	Nos	1,434.00
95	ELE-R&M-095	SITC APRV 63A,FP,415V,25KA,C TYPE MCB	Supply, Installation , testing & Commissioning of 63A,FP,415V,25KA,C TYPE MCB(MINIATURE CIRCUIT BREAKER)	ELECTRICAL	Nos	2,209.00
96	ELE-R&M-096	PRO&FIX OF FIRE BUCKETS	Fire buckets with stand-2 buckets.Bucket of round bottom,painted red,marked 'FIRE' <(>&<)> duly filled with fire river sand.	ELECTRICAL	Nos	1,889.00
97	ELE-R&M-097	SITC APRV 32A,TPN,415V,10KA,C TYPE MCB	Supply, Installation , testing & Commissioning of 32A,TPN,415V,10KA,C TYPE MCB(MINIATURE CIRCUIT BREAKER)	ELECTRICAL	Nos	1,620.00
98	ELE-R&M-098	SITC OF 20A DP MCB W/METAL ENCLOS	Supply <(>&<)> Installation of MCCB / MCB with Metal Enclosure. 20 A DP MCB with metal enclosure	ELECTRICAL	Nos	1,422.00
99	ELE-R&M-099	SITC APRV 20A,TP,415V,10KA,C TYPE MCB	Supply, Installation , testing & Commissioning o 20A,TP,415V,10KA,C TYPE MCB(MINIATURE CIRCUIT BREAKER)	ELECTRICAL	Nos	1,210.00
100	ELE-R&M-100	S&F LT DANGER APRV NOTICE BRD ELCT AUTH	Safety <(>&<)> Miscellaneous ItemsSupply and fixing in position the best quality LT Danger Boards by the local electrical authorities written in English, Hindi and local Language	ELECTRICAL	Nos	350.00
101	ELE-R&M-101	SUP&LAY CBL 1.1KV UA XLPE CU 1CX35MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , innerextruded PVC sheath ,UNARMOURED, stranded COPPER conductor cables of 1.1KV 'class cables	ELECTRICAL	Mtrs	551.00
102	ELE-R&M-102	SUP&INST OF25MM GI CONDUIT B CLASS W/ACC	Supplying and installation of 25 mm Dia, Class B Rigid GI conduit	ELECTRICAL	Mtrs	233.00
103	ELE-R&M-103	SUP&LAY CBL 1.1KV UA XLPE CU 4CX2.5MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , innerextruded PVC sheath ,UNARMOURED, stranded COPPER conductor cables of 1.1KV 'class cables	ELECTRICAL	Mtrs	270.00
104	ELE-R&M-104	SUP&LAY CBL 1.1KV ARM XLPE AL 3CX35MM2	SUP&LAY CBL 1.1KV ARM XLPE AL 3CX35MM2	ELECTRICAL	Mtrs	363.00
105	ELE-R&M-105	SUP&LAY CBL 1.1KV ARM XLPE AL 3CX50MM2	SUP&LAY CBL 1.1KV ARM XLPE AL 3CX50MM2	ELECTRICAL	Mtrs	499.00
106	ELE-R&M-106	S&L APRV PVC FLEXIBL CBL1.1KV CU3CX16MM2	S&L APRV PVC FLEXIBL CBL1.1KV CU3CX16MM2	ELECTRICAL	Mtrs	1,010.00
107	ELE-R&M-107	S&L APRV PVC FLEXIBL CBL1.1KV CU4CX35MM2	S&L APRV PVC FLEXIBL CBL1.1KV CU4CX35MM2	ELECTRICAL	Mtrs	2,355.00
108	ELE-R&M-108	S&L APRV PVC FLEXIBL CBL1.1KV CU4CX25MM	S&L APRV PVC FLEXIBL CBL1.1KV CU4CX25MM	ELECTRICAL	Mtrs	1,837.00
109	ELE-R&M-109	SITC APRV 20A,SP,230V,10KA,C TYPE MCB	SITC APRV 20A,SP,230V,10KA,C TYPE MCB	ELECTRICAL	Nos	318.00
111	ELE-R&M-111	SUP&INST HVY DTY FR PVC CONDUIT 32MM FBL	Supplying and installation of heavy duty FR PVC conduit	ELECTRICAL	Mtrs	66.50
112	ELE-R&M-112	SUP&LAY CBL 1.1KV ARM XLPE AL 3CX70MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , innerextruded PVC sheath , 3CORE, ARMOURED, stranded ALUMINIUM conductorcables of 1.1KV 'class cables per	ELECTRICAL	Mtrs	703.00
113	ELE-R&M-113	SUP&LAY CBL 1.1KV ARM XLPE AL 4CX6MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , innerextruded PVC sheath , 3.5/4 CORE, ARMOURED, stranded ALUMINIUM conductor cables of 1.1KV 'class cable	ELECTRICAL	Mtrs	214.00

ELECTRICAL WORKS						
Sr NO	SERVICE CODES	DESCRIPTION	Long Description	WBS	UOM	RATES
114	ELE-R&M-114	SUP&LAY CBL 1.1KV UA XLPE CU 1CX4MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , innerextruded PVC sheath ,UNARMoured, stranded COPPER conductor cables of 1.1KV 'class cables	ELECTRICAL	Mtrs	104.00
115	ELE-R&M-115	SUP&LAY CTR CBL 1.1KV UA CU 12CX1.5MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , innerextruded PVC sheath ,UNARMoured, stranded COPPER conductor cables of 1.1KV 'class cables	ELECTRICAL	Mtrs	530.00
116	ELE-R&M-116	SUP&LAY CTR CBL 1.1KV UA CU 4CX1.5MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , innerextruded PVC sheath ,UNARMoured, stranded COPPER conductor cables of 1.1KV 'class cables	ELECTRICAL	Mtrs	208.00
117	ELE-R&M-117	SUP&LAY CTR CBL 1.1KV UA CU 7CX1.5MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , innerextruded PVC sheath ,UNARMoured, stranded COPPER conductor cables of 1.1KV 'class cables	ELECTRICAL	Mtrs	340.00
118	ELE-R&M-118	SUP&LAY CBL 1.1KV UA XLPE CU 4CX16MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , innerextruded PVC sheath ,UNARMoured, stranded COPPER conductor cables of 1.1KV 'class cables	ELECTRICAL	Mtrs	986.00
119	ELE-R&M-119	SUP&LAY CBL 1.1KV UA XLPE CU 4CX25MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , innerextruded PVC sheath ,UNARMoured, stranded COPPER conductor cables of 1.1KV 'class cables	ELECTRICAL	Mtrs	1,473.00
120	ELE-R&M-120	SUP&LAY CBL 1.1KV ARM XLPE CU 1CX16MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , innerextruded PVC sheath ,ARMoured, stranded COPPER conductor cables of 1.1KV 'class cables	ELECTRICAL	Mtrs	354.00
121	ELE-R&M-121	SUP&LAY CTR CBL 1.1KV ARM CU 12CX1.5MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , innerextruded PVC sheath ,ARMoured, stranded COPPER conductor cables of 1.1KV 'class cables	ELECTRICAL	Mtrs	488.50
122	ELE-R&M-122	SUP&LAY CTR CBL 1.1KV ARM CU 4CX1.5MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , innerextruded PVC sheath ,ARMoured, stranded COPPER conductor cables of 1.1KV 'class cables	ELECTRICAL	Mtrs	248.00
123	ELE-R&M-123	SUP&LAY CBL 1.1KV ARM XLPE CU 4CX10MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , innerextruded PVC sheath ,ARMoured, stranded COPPER conductor cables of 1.1KV 'class cables	ELECTRICAL	Mtrs	866.00
124	ELE-R&M-124	SUP&LAY CBL 1.1KV ARM XLPE CU 4CX16MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , innerextruded PVC sheath ,ARMoured, stranded COPPER conductor cables of 1.1KV 'class cables	ELECTRICAL	Mtrs	1,199.50
125	ELE-R&M-125	SUP&LAY CBL 1.1KV ARM XLPE CU 4CX25MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , innerextruded PVC sheath ,ARMoured, stranded COPPER conductor cables of 1.1KV 'class cables	ELECTRICAL	Mtrs	1,738.00
126	ELE-R&M-126	PWR CKT LAY 3X1.5MM2 CU WIRE	PWR CKT LAY 3X1.5MM2 CU WIRE	ELECTRICAL	Mtrs	118.00
127	ELE-R&M-127	S&L APR PVC FLEXIB CBL1.1KV CU 4CX2.5MM2	Supply and Laying of 1.1 KV Grade PVC insulated FLEXIBLE cable withcopper conductor 4C x 4 sq mm Cu	ELECTRICAL	Mtrs	233.00
128	ELE-R&M-128	S&I OF RIGID MEDI DUTY PVC CONDUIT,25 MM	Supplying and installation of different sizes of Medium duty FR PVC conduit 25 MM RIGID.	ELECTRICAL	Mtrs	94.50
129	ELE-R&M-129	WIR PWR CKT S&L CU 2X4+1X4MM2, LSHF	Supply, installation, Low Smoke Halogen Free 2 x 4.0 + 1 x 4 sqmm	ELECTRICAL	Mtrs	273.50
130	ELE-R&M-130	WIR PWR CKT S&L CU 2X2.5+1X2.5MM2, LSHF	Supply, installation Low Smoke Halogen Free ,	ELECTRICAL	Mtrs	204.00
131	ELE-R&M-131	WIR PWR CKT 2X2.5+1X2.5MM2 FP200 CU	Supply, installation, testing & commissioning of circuit wiring 2X2.5+1X2.5MM2	ELECTRICAL	Mtrs	223.50
132	ELE-R&M-132	S&I OF RIGID MEDI DUTY PVC CONDUIT 25 MM	Supplying and installation of different sizes of Medium duty FR PVC conduit 25 MM RIGID.	ELECTRICAL	Mtrs	83.50
133	ELE-R&M-133	SITC APRV 20A,DP,230V,10KA,C TYPE MCB	Supply, Installation , testing & Commissioning of 20A,DP,230V,10KA,C TYPE MCB (MINIATURE CIRCUIT BREAKER)	ELECTRICAL	Nos	812.00
134	ELE-R&M-134	SITC OF 16A, DP, 230V, 10KA, 30MA, RCBO	Supply, Installation , testing & Commissioning of 16A, DP + DP 230V, 10KA, 30mA, RCBO with O/L + S/C Protection Legrand make	ELECTRICAL	Nos	2,275.00
135	ELE-R&M-135	EP65-S&I 5 Amp Plug Top	Supply and installation of 5 Amp Plug Top. Anchor Roma or approved make.	ELECTRICAL	Nos	148.00
136	ELE-R&M-136	S&L CBL 1.1KV FLEX FR PVC CU 1CX35MM2	Supply and Laying of FR PVC insulated FLEXIBLE, Stranded COPPER conductor cables of 1.1KV 'class Size: 1Cx35 mm2 Cu PVC	ELECTRICAL	Mtrs	607.50

ELECTRICAL WORKS						
Sr NO	SERVICE CODES	DESCRIPTION	Long Description	WBS	UOM	RATES
137	ELE-R&M-137	S&L CBL 1.1KV FLEX FR PVC CU 1CX25MM2	Supply and Laying of FR PVC insulated FLEXIBLE, Stranded COPPER conductor cables of 1.1KV 'clas.Size: 1cx25 mm2 Cu PVC	ELECTRICAL	Mtrs	458.00
138	ELE-R&M-138	S&L CBL 1.1KV FLEX FR PVC CU 1CX16MM2	Supply and Laying of FR PVC insulated FLEXIBLE, Stranded COPPER conductor cables of 1.1KV 'class Size: CU 1Cx16 mm2 Cu PVC	ELECTRICAL	Mtrs	345.00
139	ELE-R&M-139	S&L CBL 1.1KV FLEX FR PVC CU 1CX6MM2	Supply and Laying of FR PVC insulated FLEXIBLE, Stranded COPPER conductor cables of 1.1KV 'class Size: CU 1Cx6 mm2 Cu PVC	ELECTRICAL	Mtrs	136.00
140	ELE-R&M-140	SITC OF WALL FAN 400MM SWEEP 60W	Supply, installation, testing & commissioning of wall mounting fan with 230 volts, 50 Hz, 50-60 W, 400 mm sweep, 1300-1400 rpm. Make - Crompton Greaves, Havells, Bajaj, Usha, Orient	ELECTRICAL	Nos	3,938.50
141	ELE-R&M-141	WIR PWR CKT 2X2.5+1X1.5MM2 FRZH	Supply, installation, testing & commissioning of circuit wiring .2X2.5+1X1.5MM2	ELECTRICAL	Mtrs	169.00
142	ELE-R&M-142	S&L PWR CKT 2X4+1X2.5MM2 FRZH CU	Supply, installation, testing & commissioning of circuit wiring 2X4+1X2.5MM2	ELECTRICAL	Mtrs	230.00
143	ELE-R&M-143	SUP&LAY CU FLEX CABLE 1CX70MM2	Supply and Laying of XLPE insulated FR PVC outer sheathed , innerextruded PVC sheath ,UNARMoured, stranded COPPER conductor cables of 1.1KV 'class cables 1C X 70sq.mm Cu Flexible Cable	ELECTRICAL	Mtrs	1,011.00
144	ELE-R&M-144	SITC OF 18 W LED 6500K BATTEN	Supply, Installation, testing & Commissioning of 18 W LED, 1150-1200 mm linear batten surface mounted . Catalogue name :- 18 W LED 6500K BATTEN" Make #Hybec/Light book/PMEA/Bajaj/Asian Retail/Wipro/Argo,Phillips/Halonix	ELECTRICAL	Nos	675.00
145	ELE-R&M-145	SITC 20W/22W LED CIR REC 5700K IP55/65	Supply, Installation, testing & Commissioning of 20W / 22W LED, Circular Recessed mounted luminaire Make Make #Hybec/Light book/PMEA/Bajaj/Asian Retail/Wipro/Argo,Phillips/Halonix	ELECTRICAL	Nos	1,800.00
146	ELE-R&M-146	S&L 4CX2.5SQMM CABLE FRLS CU FLEXIBLE	SUPPLY, LAYING, TAGGING & TERMINATION OF 4C X 2.5 SQMM FRLS PVC FLEXIBLE COPPER CABLE BETWEEN HVAC IDU & ODU..	ELECTRICAL	Mtrs	238.00
147	ELE-R&M-147	S&L 2CX1SQMM FRLS SHIELDED FLEX CU CABLE	SUPPLYING, LAYING, TAGGING & TERMINATION OF SHIELDED FRLS FLEXIBLE COPPER COMMUNICATION CABLE BETWEEN HVAC IDU & ODU. CABLE SIZE SHALL BE 2C X 1 SQMM	ELECTRICAL	Mtrs	98.00
148	ELE-R&M-148	S&L 4CX1.5SQMM CABLE FRLS CU FLEXIBLE	SUPPLY, LAYING, TAGGING & TERMINATION OF 4C X 1.5 SQMM FRLS PVC FLEXIBLE COPPER CABLE BETWEEN HVAC IDU & ODU.	ELECTRICAL	Mtrs	169.00
149	ELE-R&M-149	S&L 3CX1.5SQMM CABLE FRLS CU FLEXIBLE	SUPPLY, LAYING, TAGGING & TERMINATION OF 3C X 1.5 SQMM FRLS PVC FLEXIBLE COPPER CABLE BETWEEN HVAC IDU & ODU.	ELECTRICAL	Mtrs	138.00
150	ELE-R&M-150	S&L 2C 1.5SQMM SHIELDED FRLS CU CABLE	Supplying & laying in conduit, termination of 2 Core 1.5 sqmm shielded FRLS Flexible non polarity Copper communication cable	ELECTRICAL	Mtrs	121.00
151	ELE-R&M-151	SITC OF 20 W LED 6500K BATTEN	Supply, Installation, testing & Commissioning of 20 W LED, 1150-1200 mm linear batten surface mounted . Catalogue name :- 20 W LED 6500K BATTEN" Make #Hybec/Light book/PMEA/Bajaj/Asian Retail/Wipro/Argo,Phillips/Halonix	ELECTRICAL	Nos	710.00
152	ELE-R&M-152	SITC OF 40 W LED 6500K BATTEN	Supply, Installation, testing & Commissioning of 40 W LED, 1150-1200 mm linear batten surface mounted . Catalogue name :- 40 W LED 6500K BATTEN" Make #Hybec/Light book/PMEA/Bajaj/Asian Retail/Wipro/Argo,Phillips/Halonix	ELECTRICAL	Nos	1,000.00
153	ELE-R&M-153	S&I 06/16A Digital timer	S&I 06/16A Digital timer	ELECTRICAL	Nos	3,300.00
154	ELE-R&M-154	S&I 06/16A Analog Timer	S&I 06/16A Analog Timer	ELECTRICAL	Nos	2,337.00
155	ELE-R&M-155	P&F Exhaust Fan 6"	P&F Exhaust Fan 6"	ELECTRICAL	Nos	2,450.00
156	ELE-R&M-156	P&F Exhaust Fan 9"	P&F Exhaust Fan 9"	ELECTRICAL	Nos	2,600.00
157	ELE-R&M-157	P&F Exhaust Fan 12"	P&F Exhaust Fan 12"	ELECTRICAL	Nos	3,300.00
158	ELE-R&M-158	P&F Ceiling Fan 48"	Supply & fixing ceiling fan with fan hook fixing as per drawing - 48"	ELECTRICAL	Nos	2,550.00
159	ELE-R&M-159	P&F Ceiling Fan 24"	Supply & fixing ceiling fan with fan hook fixing as per drawing - 24"	ELECTRICAL	Nos	2,550.00